

MONUMENT				
TYPE NUMBER	STONE MARK	LOCATION	DISPOSITION	ITEM NUMBER
<b>CORRIGAN STREET</b>				
RCS 047470109	GRANITE DH	NE CORNER CORRIGAN AND ESTES	RESET EXIST MONUMENT FRAME AND COVER TO GRADE	S626.07
RCS 047470107	MEDINA DH / +	NW CORNER CORRIGAN AND LAKE	RESET EXIST MONUMENT FRAME AND COVER TO GRADE	S626.07
<b>HINCHER STREET</b>				
RCS 047460203	MEDINA DH	NE CORNER HINCHER AND FORMER RUGGLES	ADJUST TOP OF EXIST STONE AND RESET EXIST MONUMENT FRAME AND COVER TO GRADE	S626.04
RCS 047470110	MEDINA DH	NE CORNER HINCHER AND ESTES	RESET EXIST MONUMENT FRAME AND COVER TO GRADE	S626.07
RTS 047460204	CONCRETE	SOUTHSIDE HINCHER - STATION H13+70 RIGHT	SET NEW RTS MONUMENT WITH NEW FRAME AND COVER	S626.03
RCS 047470105	MEDINA DH	NW CORNER HINCHER AND LAKE	RESET EXIST MONUMENT FRAME AND COVER TO GRADE	S626.07
<b>FLEMING STREET</b>				
RCS 047460201	GRANITE DH	NW CORNER FLEMING AND ESTES	RESET EXIST MONUMENT FRAME AND COVER TO GRADE	S626.07
NOTE: ALL EXISTING MONUMENTS ARE TO BE PROTECTED DURING CONSTRUCTION IF EXIST RCS MONUMENT 47460203 CANNOT BE VERTICALLY ADJUSTED, EXIST MONUMENT IS TO BE REMOVED AND NEW RCS MONUMENT WITH NEW FRAME AND COVER IS TO BE SET AT DIRECTION OF CITY SURVEY OFFICE.				

HYDRANT		
STATION	DISPOSITION	ITEM NUMBER
<b>CORRIGAN STREET</b>		
C13+22 LT	EXIST HYDRANT TO REMAIN - NO WORK ANTICIPATED	---
<b>HINCHER STREET</b>		
H10+33 LT	REMOVE EXIST HYDRANT ASSEMBLY, HYDRANT MARKER POST, VALVE BOX	S917.05
H10+80 LT	INSTALL NEW HYDRANT ASSEMBLY, 6" PVC PIPE, 6" GATE VALVE AND 6" x 6" TEE (RESTRAIN ALL JOINTS) HYDRANT MARKER WILL BE INSTALLED BY OTHERS	S917.01
H12+79 LT	EXIST HYDRANT TO REMAIN - NO WORK ANTICIPATED	---
H16+59 LT	EXIST HYDRANT TO REMAIN - NO WORK ANTICIPATED	---
<b>RUGGLES STREET</b>		
RF10+62 LT	EXIST HYDRANT TO REMAIN - NO WORK ANTICIPATED	---
<b>FLEMING STREET</b>		
RF12+44 LT	EXIST HYDRANT TO REMAIN - NO WORK ANTICIPATED	---
RF15+77 LT	EXIST HYDRANT TO REMAIN - NO WORK ANTICIPATED	---

DRIVEWAY APRON				
ADDRESS	HEADER CURB LENGTH	APRON PAVEMENT TYPE	COMMENTS	ITEM NUMBER
<b>CORRIGAN STREET</b>				
40 CORRIGAN	15'	ASPHALT	---	S608.15
36 CORRIGAN 30 CORRIGAN	15'	ASPHALT	COMMON APRON	S608.15
35 CORRIGAN	12'	ASPHALT	---	S608.15
33 CORRIGAN 27 CORRIGAN	15'	ASPHALT	COMMON APRON	S608.15
24 CORRIGAN	12'	ASPHALT	---	S608.15
23 CORRIGAN	12'	ASPHALT	---	S608.15
19-15 CORRIGAN	12'	ASPHALT	---	S608.15
4753-4759 LAKE	24'	EXPOSED AGGREGATE	5' TRANSITION CURB BOTH SIDES	S608.37
4739 LAKE	12'	ASPHALT	---	S608.15
<b>HINCHER STREET</b>				
CYAA FIELDS	24'	ASPHALT	MEDIUM-DUTY	S608.16
77 HINCHER	12'	ASPHALT	---	S608.15
69 HINCHER	12'	ASPHALT	---	S608.15
59 HINCHER	12'	ASPHALT	---	S608.15
25-23 HINCHER	12'	ASPHALT	---	S608.15
24 HINCHER	12'	ASPHALT	---	S608.15
22 HINCHER	12'	ASPHALT	---	S608.15
19 HINCHER	12'	ASPHALT	---	S608.15
4721-4723 LAKE	18'	ASPHALT	---	S608.15
<b>RUGGLES STREET</b>				
83 LAKELAND	24'	CONCRETE	---	S608.14
82 LAKELAND	14'	ASPHALT	---	S608.15
<b>FLEMING STREET</b>				
80 FLEMING	12'	ASPHALT	---	S608.15
76 FLEMING	12'	ASPHALT	---	S608.15
59 FLEMING	12'	ASPHALT	---	S608.15
54 FLEMING	12'	ASPHALT	---	S608.15
51 FLEMING	12'	ASPHALT	---	S608.15
50 FLEMING	12'	ASPHALT	---	S608.15
49 FLEMING	12'	ASPHALT	---	S608.15
48 FLEMING	12'	ASPHALT	---	S608.15
46 FLEMING	12'	ASPHALT	---	S608.15
45 FLEMING	18'	ASPHALT	2 CAR GARAGE	S608.15
33 FLEMING	14'	EXPOSED AGGREGATE	5' TRANSITION CURB BOTH SIDES	S608.37
27 FLEMING	14'	EXPOSED AGGREGATE	5' TRANSITION CURB BOTH SIDES	S608.37
25 FLEMING	14'	EXPOSED AGGREGATE	5' TRANSITION CURB BOTH SIDES	S608.37
<b>ESTES STREET</b>				
51 HINCHER	22'	ASPHALT	2 CAR GARAGE	S608.15
<b>LAKE AVENUE</b>				
4667 LAKE	32'	EXPOSED AGGREGATE	24' AT SIDEWALK 5' TRANSITION CURB BOTH SIDES	S608.37

STREET LIGHTING			
STATION	DISPOSITION	ITEM NUMBER	
<b>HINCHER STREET</b>			
H13+04 LT	ADJUST EXIST HANDHOLE/PULLBOX TO GRADE	S671.1701	
H15+58 RT	INSTALL RISER CONNECTION ON EXIST WOOD POLE (WLP1)	S671.0801	
H16+56 RT	INSTALL NEW PRECAST FOUNDATION	S671.3201	
<b>FLEMING STREET</b>			
RF17+53 RT	INSTALL RISER CONNECTION ON EXIST WOOD POLE (WLP3)	S671.0801	
RF17+90 LT	INSTALL NEW PRECAST FOUNDATION	S671.3201	
RF18+27 LT	INSTALL NEW PRECAST FOUNDATION	S671.3201	
RF18+64 LT	INSTALL NEW PRECAST FOUNDATION	S671.3201	
<b>ESTES STREET</b>			
E13+15 RT	ADJUST EXIST HANDHOLE/PULLBOX TO GRADE	S671.1701	
E13+15 LT	EXIST FLP1 1 TO REMAIN - NO WORK ANTICIPATED	---	
E15+04 RT	EXIST PULLBOX TO REMAIN - NO WORK ANTICIPATED	---	
E15+85 RT	EXIST FLP8 TO REMAIN - NO WORK ANTICIPATED	---	
NOTE: CONTRACTOR TO INSTALL NEW FOUNDATIONS, CONDUIT AND RISER CONNECTIONS. CITY'S STREET LIGHTING CONTRACTOR WILL INSTALL LIGHT POLES, FIXTURES AND CABLE, AND DO ALL WIRING.			

WATER SERVICE				
ADDRESS	EXIST SERVICE		DISPOSITION	ITEM NUMBER
	STATION	SIZE-TYPE		
<b>CORRIGAN STREET</b>				
40 CORRIGAN	C10+65	3/4" COPPER	ADJUST EXISTING CURB BOX TO GRADE	
36 CORRIGAN	C11+14	3/4" COPPER	ADJUST EXISTING CURB BOX TO GRADE	
35 CORRIGAN	C10+74	3/4" COPPER	ADJUST EXISTING CURB BOX TO GRADE	
33 CORRIGAN	C11+13	3/4" COPPER	ADJUST EXISTING CURB BOX TO GRADE	
30 CORRIGAN	C11+58	3/4" COPPER	ADJUST EXISTING CURB BOX TO GRADE	
27 CORRIGAN	C11+50	3/4" COPPER	ADJUST EXISTING CURB BOX TO GRADE	
24 CORRIGAN	C12+01	3/4" COPPER	ADJUST EXISTING CURB BOX TO GRADE	
23 CORRIGAN	C12+01	3/4" COPPER	ADJUST EXISTING CURB BOX TO GRADE	
19-15 CORRIGAN	C12+62	3/4" COPPER	REMOVE EXIST CURB BOX (ITEM 203.02) AND INSTALL NEW 3/4" CURB STOP AND BOX	
4739 LAKE	C12+93	3/4" COPPER	REMOVE EXIST CURB BOX (ITEM 203.02) AND INSTALL NEW 3/4" CURB STOP AND BOX	
4753-4759 LAKE	C12+91	3/4" COPPER	REMOVE EXIST CURB BOX (ITEM 203.02) AND INSTALL NEW 3/4" CURB STOP AND BOX	
<b>HINCHER STREET</b>				
77 HINCHER	H10+77	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
69 HINCHER	H11+26	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
59 HINCHER	H12+23	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
51 HINCHER	H12+66	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
26 HINCHER	H14+39	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
24 HINCHER	H14+68	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
23 HINCHER	H14+68	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
22 HINCHER	H15+27	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
19 HINCHER	H14+73	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
17 HINCHER	H15+04	3/4" COPPER	RUN SERVICE - DO NOT RENEW - REMOVE EXIST CURB BOX (ITEM S608.15)	
15 HINCHER	H15+35	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
<b>RUGGLES STREET</b>				
83 LAKELAND	RF9+70	3/4" COPPER	ADJUST EXISTING CURB BOX TO GRADE	
82 LAKELAND	RF10+41	3/4" COPPER	ADJUST EXISTING CURB BOX TO GRADE	
<b>FLEMING STREET</b>				
80 FLEMING	RF12+87	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
76 FLEMING	RF13+12	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
59 FLEMING	RF12+70	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
54 FLEMING	RF14+81	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
51 FLEMING	RF13+13	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
50 FLEMING	RF13+53	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
49 FLEMING	RF13+52	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
48 FLEMING	RF13+99	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
46 FLEMING	RF14+49	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
45 FLEMING	RF14+46	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
33 FLEMING	RF15+98	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
27 FLEMING	RF16+40	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
25 FLEMING	RF16+96	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
22 FLEMING	RF17+02	3/4" COPPER	INSTALL NEW 1" SERVICE TAP, POLYETHYLENE WATER SERVICE, CURB STOP AND BOX	
18 FLEMING	RF17+80	3/4" COPPER	REMOVE EXIST CURB BOX (ITEM 203.02)	

NOTE: PRIOR TO COMMENCING WORK, CONTRACTOR IS TO VERIFY LOCATION AND DISPOSITION OF ALL WATER SERVICE WORK.

ITEM: ALL ITEMS INCLUDE EXCAVATION AND BACKFILL

- S912.020100 - NEW 1" WATER SERVICE TAP
- S913.120100 - NEW 1" POLYETHYLENE WATER SERVICE PIPE
- S914.020100 - NEW 1" CURB STOP AND BOX
- S914.050034 - NEW 3/4" CURB STOP AND BOX AT EXISTING WATER SERVICE
- S914.14 - ADJUST EXISTING CURB BOX

WATER VALVE		
STATION	DISPOSITION	ITEM NUMBER
<b>CORRIGAN STREET</b>		
C10+47 LT	ADJUST EXIST WATER VALVE BOX TO GRADE	S909.08
C13+19 LT	ADJUST EXIST WATER VALVE BOX TO GRADE	S909.08
C13+22 LT	ADJUST EXIST WATER VALVE BOX TO GRADE	S909.08
C13+27 LT	ADJUST EXIST WATER VALVE BOX TO GRADE	S909.08
C13+27 LT	ADJUST EXIST WATER METER PIT TO GRADE	S914.23
C13+27 LT	ADJUST EXIST WATER VALVE BOX TO GRADE	S909.08
<b>HINCHER STREET</b>		
H10+27 LT	REMOVE EXIST WATER VALVE BOX (NO SEPARATE PAYMENT)	203.02
H10+27 LT	INSTALL NEW 6" RESILIENT SEAT GATE VALVE AND VALVE BOX	S903.0106
H10+28 LT	REMOVE EXIST WATER VALVE BOX (NO SEPARATE PAYMENT)	S917.05
H10+80 LT	INSTALL NEW 6" RESILIENT SEAT GATE VALVE AND VALVE BOX	S903.0106
H12+79 LT	ADJUST EXIST WATER VALVE BOX TO GRADE	S909.08
H13+78 LT	INSTALL NEW 6" RESILIENT SEAT GATE VALVE AND VALVE BOX	S903.0106
H16+61 LT	ADJUST EXIST WATER VALVE BOX TO GRADE	S909.08
H16+65 LT	ADJUST EXIST WATER VALVE BOX TO GRADE	S909.08
H17+02 LT	EXIST WATER VALVE BOX TO REMAIN - NO WORK ANTICIPATED	---
<b>RUGGLES STREET</b>		
RF10+62 LT	ADJUST EXIST WATER VALVE BOX TO GRADE	S909.08
<b>FLEMING STREET</b>		
RF12+41 LT	INSTALL NEW 6" RESILIENT SEAT GATE VALVE AND VALVE BOX	S903.0106
RF12+42 LT	REMOVE EXIST WATER VALVE BOX (NO SEPARATE PAYMENT)	203.02
RF12+52 LT	REMOVE EXIST WATER VALVE BOX (NO SEPARATE PAYMENT)	203.02
RF12+52 LT	INSTALL NEW 6" RESILIENT SEAT GATE VALVE AND VALVE BOX	S903.0106
RF15+72 LT	ADJUST EXIST WATER VALVE BOX TO GRADE	S909.08
RF19+23 LT	REMOVE EXIST WATER VALVE BOX	S909.05
RF19+24 LT	INSTALL NEW 6" RESILIENT SEAT GATE VALVE AND VALVE BOX	S903.0106

TRACER WIRE TERMINATION BOX		
STATION	DISPOSITION	ITEM NUMBER
<b>HINCHER STREET</b>		
H10+77 LT	INSTALL NEW TRACER WIRE TERMINATION BOX	S901.130106
H12+76 LT	INSTALL NEW TRACER WIRE TERMINATION BOX	S901.130106
H13+72 LT	INSTALL NEW TRACER WIRE TERMINATION BOX	S901.130106
H16+56 LT	INSTALL NEW TRACER WIRE TERMINATION BOX	S901.130106
<b>FLEMING STREET</b>		
RF12+44 LT	INSTALL NEW TRACER WIRE TERMINATION BOX	S901.130106
RF15+00 RT	INSTALL NEW TRACER WIRE TERMINATION BOX	S901.130106
RF15+74 LT	INSTALL NEW TRACER WIRE TERMINATION BOX	S901.130106
RF19+13 LT	INSTALL NEW TRACER WIRE TERMINATION BOX	S901.130106

SIGN SLEEVE			
ADDRESS	STATION	DISPOSITION	ITEM NUMBER
<b>CORRIGAN STREET</b>			
4753-4759 LAKE	C12+78 LT	INSTALL NEW SIGN SLEEVE	S643.0101
<b>FLEMING STREET</b>			
54 FLEMING	RF14+84 LT	INSTALL NEW SIGN SLEEVE	S643.0101

TREE REMOVAL			
ADDRESS	STATION	TREE SIZE AND SPECIES	ITEM NUMBER
<b>HINCHER STREET</b>			
FORMER RUGGLES	H10+33 RT	16"	S614.36
	H10+35 RT	16"	S614.36
	H10+42 LT	12"	S614.36
	H10+62 LT	12"	S614.36
<b>RUGGLES STREET</b>			
59 FLEMING	RF12+10 RT	36" OAK	S614.40
<b>FLEMING STREET</b>			
24 FLEMING	RF17+07 LT	24"	S614.38
<b>LAKE AVENUE</b>			
4667 LAKE	L9+43 LT	4"	203.02

TREE PLANTING			
ADDRESS	STATION	TREE SPECIES COMMON NAME	ITEM NUMBER
<b>CORRIGAN STREET</b>			
27 CORRIGAN	C11+65 RT	Pyrus calleryana 'Chanticleer' - CHANTICLEER PEAR	S611.0403
23 CORRIGAN	C12+13 RT	Acer rubrum 'Red Sunset' - 'RED SUNSET' RED MAPLE	S611.0402
15-19 CORRIGAN	C12+55 RT	Amelanchier x grandiflora 'Robin Hill' (pink) - tree form - ROBIN HILL SERVICEBERRY	S611.0404
<b>HINCHER STREET</b>			
TURN-AROUND	H9+85 RT	Acer x fremanii 'Armstrong' - ARMSTRONG FREEMAN MAPLE	S611.0401
35 HINCHER	H13+85 RT	Amelanchier x grandiflora 'Robin Hill' (pink) - tree form - ROBIN HILL SERVICEBERRY	S611.0404
4705 LAKE HINCHER ST SIDE	H16+05 RT	Pyrus calleryana 'Chanticleer' - CHANTICLEER PEAR	S611.0403
<b>ESTES STREET</b>			
54 FLEMING ESTES ST SIDE	E10+50 LT	Amelanchier x grandiflora 'Robin Hill' (pink) - tree form - ROBIN HILL SERVICEBERRY	S611.0404
	E10+75 LT	Pyrus calleryana 'Chanticleer' - CHANTICLEER PEAR	S611.0403

Department of Environmental Services Architecture and Engineering Services City of Rochester, New York				ALBERT J. GIUGLIOPPE JAMES R. MONTOSH, P.E. MANAGING ENGINEER CITY ENGINEER				
<b>STREET IMPROVEMENT PROGRAM</b> <b>HINCHER GROUP</b>								
PROJECT TITLE	ISSUED	CHECKED	DRAWN	DESIGN	SCALE	PROJECT NUMBER	BY	DATE
STREET IMPROVEMENT PROGRAM HINCHER GROUP	JUNE 1, 2015	LYR	RKS	LYR	NONE	12/109	NO.	REVISION
<b>TABLES</b>								
DRAWING NO.				10				
OF				50				